

**Interior Job Estimation for the site of**  
**Kamarpukur Br. (H.D.C.C.B)**

**Date – 04.04.2022**

<b><u>SL NO:</u></b>	<b><u>ITEM DESCRIPTIONS</u></b>	<b><u>QTY</u></b>	<b><u>UNIT</u></b>
1.	Providing and fixing of partition made by waterproof ply, both side laminate finish With necessary fittings and labour charges for counter area. (13'0" X 5'0"), (70'0" X 9'0") <b>Ply Specification– Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	695	Sft.
2.	Providing and fixing of 2'-6" width 3nos running teller counter with top made of 19mm plywood thick on top and upper counter made by 8mm clear glass. The table top to include with two pencil drawer of 100 mm deep & a fine shutter of 450mm and key board tray, With both side laminate finish. CPU box wire managers and all necessary hardware fittings. <b>Ply Specification– Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	14	Rft
3.	Providing and fixing of 2'-6" width 1no cashier counter with top made of 19mm plywood thick on top Wooden lipping all round and all necessary hardware fittings with both side laminate finish. (6'0" x 2'6") <b>Ply Specification– Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	15	Sft
4.	Providing and fixing of file cabinet made by commercial waterproof ply, both side laminate, necessary fittings and labour charges. (15'0" x 3'6"), (6'0" x 3'6"), (8'6" x 9'0"), (8'6" x 2'6") <b>Ply Specification– Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	171	Sft.
5.	Providing and fixing of 2'-6" width Supervisor and Manager's table with top made of 19mm commercial plywood on top Wooden lipping all round. The table top to include pedestal with two pencil drawer of 100 mm deep & a fine shutter of 450mm and key board tray with both side laminate finish. CPU box wire managers and all necessary hardware fittings and fixture etc.(5'6" x 2'6" x 2 Nos) <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	28	Sft

6.	Providing and fixing of supervisor and Manager's side table with a fine sliding palla made by commercial waterproof ply, both side laminate, necessary fittings and labour charges. (3'0" x 2'3" x 1 No) <b>Ply Specification- Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	7	Sft.
7.	Providing and fixing of 2'-0" width Server room table with top made of 19mm commercial plywood on top Wooden lipping all round. The table top to include pedestal with one pencil drawer of 100 mm deep & a fine shutter of 550mm and key board tray with both side laminate finish. CPU box wire managers and all necessary hardware fittings and fixture etc.(8'6" x 2'6") <b>Ply Specification- Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	21	Sft
8.	Providing and fixing of 7 Nos flush door made by commercial waterproof ply, laminate, glass, Door closer, Handle, stopper necessary fittings and labour charges. (7'0" x 3'0" x 6 Nos), (5'0" X 3'0" x 1 No) <b>Ply Specification- Bell, Samrat, Trandz, Satabdi etc.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	141	Sft.
9.	Supply and fixing Window Blinds of Vertical Blinds made of 100% Polymer coating. <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	200	Sft
10.	Providing and fixing of Gypsum plain false ceiling made by gypsum board with properly hanged with gi frame work, finish with compound pest. <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	1000	Sft
11.	Providing and fixing of Grid false ceiling made by 2'0" x 2'0" Armstrong grid board with properly hanged with gi frame work. <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	300	Sft
12.	Supplying and applying of Premium Emulsion Paint of entire wall with labour and materials. (2 coat primer and 2 paint)  <b>Paint – Asian Paint/Burger.</b> <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	5500	Sft



13.	Suppling and Appling of iron base collapsible gate for entrance of bank area with material and labour charges. (7'6" x 5'6"),(7'4" x 3'6") <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	322	Kg
14.	Providing and fixing of required all electrical materials to complete the wiring with all necessary itemsand labour charges. <b>(M.C.B, CEILING LIGHT, WALL FAN, SWITCH BOARD, POWER POINT)</b> Wire- Havells/Finolex Switch Board- Crabtree/Equivalent. Main Switch – Havells. MCB – Havells. Wall Fan – Havells. Ceiling Lights – Havells.  <b>(TO BE DONE UNDER SPECIFIC INSTRUCTION OF BANK ENGINEER)</b>	1600	Sft
15.	Revolving Chair (For Officers)	6	Nos
16.	Visitors Chair	6	Nos
17.	S.S Lobby Chair (3 Nos/Set)	02	Set
18.	Centre Table	02	Nos
19.	Providing and fixing of soft board (4'0" x 4'0")	16	Sft